Bruhat Bangalore Mahanagara Palike
Excecutive Engineer Yelahanka Project Division

Name of Work: Supply and Installation of Shredder in Yelahanka Zone BBMP
(Near Bio Plant, Near BWSSB Office , Behind Police station, Gundanjaneya Temple, NearRailway Track)

ESTIMATE

Item No.	Description	Unit	No.	Length, m	Width, m	Depth, m	Quantity	Rate, Rs	Amount, Rs
1	Supplying and Fixing Shredder of Make - Stainless Steel, 3mm sheet with crushing body made out cylindrical plates of 8 - 10mm thick attached with 40 no SS hardened blades with 35mm shaft of length 2.5 feet, with mesh opening of 19mm dia, capacity to handle all types of dry leaves. Power - 5Hp 3 Phase, Material Handle - Handle all types of segregated dry leaves waste .1-2 ton/day Size - 3*4feet, height 4 feet (With 2 years of Maintenance and Including all taxes)								
	Approved Data Rate	249000.00							
		Unit	5				5.00		
							5.00	**249000.00**	**1245000.00**
	Miscellaneous & Roundoff								5000.00
								Total Cost , Rs.	**1250000.00**

Assistant Engineer,
Yelahanka Project Division

Asst. Exec. Engineer,
Yelahanka Project Division
24/7/18

Executive Engineer,
Yelahanka Project Division

Administrative Approval
Accorded For Rs. 12.50 lakhs only
Head of A/C P-3158
CER NO :.....01..... Dt: 25/07/18
H.V.
E.E. (Project)

Technical Sanction
Accorded For Rs. 12.50 lakhs
Head of A/C P-3158
CER NO :.....01..... Dt: 25/07/18
H.V.
E.E. (Project)